

# CITY OF SANTA FE

Public Works Department

## INVITATION TO BID Amendment No. 1



**ITB # 23/19/B**

**Amendment Issue Date: December 30, 2022**

**Title: Erosion Control and Bank Repair at Arroyo de Los Chamisos North Fork**

**BID DUE DATE AND TIME: January 17<sup>th</sup>, 2022 at 2:00 PM**

**ELECTRONIC-ONLY PROPOSAL SUBMISSION**

## **Erosion Control and Bank Repair at Arroyo de Los Chamisos North Fork**

**ITB# 23/19/B**

### **Amendment No.1**

1. This Amendment is issued to correct the following missing bid items and quantities listed in the Bid Sheet (See \*Revised Price Schedule for both Site #1 & Site #2):

- Reseeding
- Flowable Fill

2. Also corrected is the note on Sheet 5-2 regarding Flowable Fill:

The use of flowable fill will be determined in the field as coordinated with the contractor and project engineer if voids behind existing structures can't be addressed with soil backfill operations.

Please acknowledge receipt of this AMENDMENT with your ITB.

It shall be the responsibility of interested bidders to adhere to any changes or revisions to the ITB as identified in this Amendment No. 1.

**Specifications:**

The City of Santa Fe is seeking bids for the Erosion Control and Bank Repair at Arroyo de Los Chamisos North Fork – Site 1 and Site 2. Site 1 consists of erosion control and repair near the intersection of Alamosa Drive and Santa Clara Drive. Site improvements include a new wire enclosed riprap swale and rundown, gabion walls, and a minor diversion berm.

Site 2 includes repair or removal and replacement of the gabion walls, concrete wing walls, and the existing plunge basin / energy dissipator which have failed due to previous runoff events.

**\*Revised Price Schedule:**

**Site 1:**

<b>Item</b>	<b>Approx. QTY</b>	<b>Unit</b>	<b>Article and Description</b>	<b>Unit Price</b>
1	15	C.Y.	UNCLASSIFIED EXCAVATION	\$
2	5	C.Y.	EMBANKMENT FILL	\$
3	1	L.S.	REMOVAL OF STRUCTURES AND OBSTRUCTIONS	\$
4	13	C.Y.	WIRE ENCLOSED RIP RAP	\$
5	81	C.Y.	GABIONS	\$
6	20	L.F.	MULCH SOCKS	\$
7	0.1	AC.	CLASS A SEEDING	\$
8	1	L.S.	SWPP PLAN PREPARATION / LEW	\$
9	1	L.S.	MOBILIZATION	\$
10	1	L.S.	TRAFFIC CONTROL	\$
11	1	L.S.	ASBUILT DRAWINGS	\$
12	1	L.S.	CONSTRUCTION STAKING	\$
13	1	L.S.	CONSTRUCTION TESTING	\$

**Site 2:**

<b>Item</b>	<b>Approx. QTY</b>	<b>Unit</b>	<b>Article and Description</b>	<b>Unit Price</b>
1	270	C.Y.	UNCLASSIFIED EXCAVATION	\$
2	125	C.Y.	EMBANKMENT FILL	\$
3	6	C.Y.	FLOWABLE FILL	\$
4	75	S.Y.	BASECOURSE TYPE II - 6"	\$
5	1	L.S.	REMOVAL OF STRUCTURES AND OBSTRUCTIONS	\$
6	105	C.Y.	WIRE ENCLOSED RIPRAP	\$
7	615	C.Y.	GABIONS	\$
8	40	L.F.	MULCH SOCKS	\$
9	0.1	AC.	CLASS A SEEDING	\$

<b>Item</b>	<b>Approx. QTY</b>	<b>Unit</b>	<b>Article and Description</b>	<b>Unit Price</b>
10	1	L.S.	SWPP PLAN PREPARATION / LEW	\$
11	1	L.S.	MOBILIZATION	\$
12	1	L.S.	TRAFFIC CONTROL	\$
13	1	L.S.	ASBUILT DRAWINGS	\$
14	1	L.S.	CONSTRUCTION STAKING	\$
15	1	L.S.	CONSTRUCTION TESTING	\$

END: Amendment No.1